

BILLS OF QUANTITIES FOR THE RENOVATION OF OFFICE AT MINISTRY OF DISASTER MANAGEMENT

ITEM	DESCRIPTION	UNIT	QTY	RATE (Rs)	AMOUNT (Rs)
1.00	Ceiling work				
1.01	Removing of existig damaged 9mm gypsum board ceiling & installation of new 9mm gypsum board ceiling with all accessories .	Sq.Ft	650.00		
2.00	Aluminum work				
2.01	Removing and replacing of exsiting Aluminium (3" x 1.5") glass/gypsum partition and adding new Aluminium glass/gypsum partition .	Lft	20.00		
3.00	Painting Work				
3.01	Prepare of damaged wall edges and apply two coats of emulsion paint (Brilliant white) in internal walls.	Sq.Ft	650.00		
3.02	Prepare of existing ceiling boards & new ceiling boards , apply two coats of emulsion paint (Brilliant white) .	Sq.Ft	700.00		
3.03	Prepare of existing aluminum partition board & new partition boards , apply two coats of emulsion paint (Brilliant white) .	Sq.Ft	75.00		
4.00	Floor Finishes				
4.01	Supply and installation 6-8 mm thick of high quality Washable, Reversible, stain Resistant, Non-Slip,loop pile cushion floor carpet (Colour & Design approved by Client)	Sq.Ft	690.00		
5.00	Electrical Work				
5.01	Supply and install 2.5mm ² PVC cable and 2.5mm ² earth conductor through the slab & wall PVC conduit including PVC conduit, sunk box & other accessories for 13A Socket outlet.	Nos	7.00		
6.00	Timber Work				
6.01	Supply of Teak colour mat finished Hard wood timber (Class 1 or above) rack (7' x 6') with five	Nos	1.00		
TOTAL					

5/6/23